

Notes

- 1" line sits in creole of the Aframe and is held in place by friction.
- The A-frame is not guyed upright. As the tower is erected, the A-frame leans towards the ground and falls away when the tower reaches an angle of about 45°.
- The legs of the tower are tied back to prevent it from sliding during the early stages of the lift.
- A safety line to prevent the tower from being pulled past vertical is not shown.
- All hooks and snatch blocks are moused shut with binder twine.

